Registered No. M.—1175.

215

417

The Mysore Gazette.

Vol. 55.] PUBLISHED BY AUTHORITY. [No. 17.

BANGALORE, THURSDAY, APRIL 22, 1920.

PART VI.

PUBLIC ADVERTISEMENTS.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 13th April 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 noon on 10th May 1920, for restoring Thandramakalahalli Tank Registered No. 61 of Chikballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash as earnest money and be superscribed "Tender for restoring Thandramakalahalli Tank Registered No. 61 of Chikballapur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Approximate quantities for restoring Thandramakalahalli Tank Registered No. 61 of Chikballapur Taluk.

No.	Bund	Per	Quantity
1	Earthwork with consolidation	C. yd.	7,543
2	Cutting trenches to receive new earth	Lump	sum
3	Excavation for revetment and using the earth to bund	C. yd.	214
4	Turfing	S. yd.	5,643
5	Grade stones with bed slab stones including chiselling, painting, etc., complete	No.	22
6	Do Index stones	,,	22
7	Registered No. stone	,,	1
8	B. M. stone	,,	2
9	Date stone	,,	1
10	Gauge stone	,,	1
11	Old stone work	C. yd.	133
12	New stone work	,,	1,574
	Sluice No. 1.		
1	Earthwork cutting bund and refilling the same with consolidation	C. yd.	68
2	Concrete in surki mortar	C. ft.	186
3	Burnt brick in surki mortar	,,	421
4	Burnt stone slabs dressed	S. ft.	139
5	Cutting to orifice slabs	Lump	sum
6	Surki plastering	Sq.	3·32
7	Putting plug and rods, etc., complete	Lump	sum
	Sluice No. 2.		
	As per sluice No. 1 above.		
	Constructing waste weir 125 feet long.		
1	Earthwork excavation and using the same to bund with consolidation	C. yd.	503
2	Concrete in surki mortar	C. ft.	529
3	Burnt brick in surki mortar	,,	1,481
4	Burnt stone slabs dressed	S. ft.	598
5	Surki plastering	Sq.	7
6	New stone work	C. yd.	337
7	Jaggles	No.	24

V. V. KARVE,
Executive Engineer.

MYSORE DIVISION.

Dated 7th April 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th May 1920 for constructing a Dispensary with out-houses at Bettadpur, Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money and be superscribed, "Tender for constructing a Dispensary with out-houses at Bettadpur, Hunsur Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6 Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable cost of constructing a Dispensary with out-houses at Bettadpur, Hunsur Taluk :—

No.	Items of work	Per	Quantity
	Dispensary buildings—		
1	Earthwork excavation	C. yd.	74
2	Brick in mortar	C. ft.	4,999
3	Brick in mortar archwork	"	99
4	Burnt stone slabs 6" thick and dressed	S. ft.	350
5	Cut stone pillars with cops and bases complete	Each	10
6	Masonry mouldings at ends	"	2
7	Plastering with mortar	Sqr.	39·26
8	Whitewashing	"	23·39
8A	Colourwashing as per exterior plastering	"	15·87
9	Teakwood panelled door without bottom rail hinges complete	S. ft.	126
10	Teakwood windows panelled shutters and iron bars ¾" with hinges, etc., complete.	"	30
10A	Windows with iron bars of ¾" *dia* panelled and glazed shutters with hinges complete.	"	27
11	Ventilator with glazed shutters	"	13
12	Circular ventilator	"	115·72
13	Teakwood wrought and putup	C. ft.	19·20
14	Roofing with first class Mangalore tiles over teak reepers complete	Sqr.	80
15	Ridge tiles set in mortar and cement pointing	R. ft.	44
16	Zinc sheets for valley	S. ft.	44
17	Teakwook plank ½" thick	S. ft.	262
18	Eave board 9" high ornamental	R. ft.	25
19	Cornice 3" complete	"	18·15
20	Wood oiling two coats	Sqr.	8·89
21	Chacolate painting	"	4
22	Teakwood finials	Each	87
23	Teakwood shelf plank of 1½" in thickness	S. ft.	4·29
24	Flooring with 9" square Mangalore tiles over 3" concrete and cement pointing.	Sq.	4·61
25	Flooring with Kadapa slabs" over 3" concrete and cement pointing	"	2
26	Constructing cisterns	Each	
27	Clearing sites	Lump sum	
	Kitchen—		
1	Earthwork excavation	C. yd.	4
2	Brick in chunnam	C. ft.	454
3	Burnt stone slabs 6" thick and dressed	S. ft.	23
4	Plastering with chunnam	Sq.	5·83
5	White and coourwashing	"	5·83
6	Teakwood battened door complete	S. ft.	18
7	Teakwood battened windows with iron bars complete	"	4½
8	Teakwood wrought and putup	C. ft.	7·97
9	Roofing with first class Mangalore tiles over teak reepers	Sq.	2·29
10	Ridge tiles set in mortar cement pointing	R. ft.	15
11	Teakwood plain eave board (6")	"	60
12	Wood oiling two coats	S. ft.	0·74
13	Chacolate painting two coats	"	1·05
14	Flooring with Kadapa slabs over 3" concrete and cement pointing	Sq.	0·32
15	Constructing cistern and oven	Lump sum	
16	Ventilating tiles, etc.	Each	4
	Latrine—		
1	Earthwork excavation	C. yd.	4
2	Burnt brick in mortar	C. ft.	362
3	Coping with burnt brick in mortar and plastering complete	R. ft.	40
4	Plastering with mortar	Sq.	4.26
5	Tarring	"	1·08
6	Flooring with Kadapa slabs over 3" concrete and cement pointing	"	0·63

A. PUTTUSAMIAH,
Executive Engineer.

SHIMOGA DIVISION.

Dated 16th April 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 31st May 1920, for restoring the Kunetappa Doddakere, Registered No. 121 of Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender

for restoring the Kunetappa Doddakere, Registered No. 121 of Sorab Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of restoring the Kunetappa Doddakere tank, Registered No. 121 of Sorab Taluk, Shimoga District.

No.	Items of work	Per	Quantity
	I Bund at R. L. 55·000—		
1	Clearing bushes and scraping grass for the new earthwork	Lump	sum Rs.
2	Earthwork to bund excluding watering tamping	C. yd.	10,423
3	Turfing the front and rear slopes of the bund, etc., complete ..	S. yd.	9,521
4	Providing and fixing grade stones with bed slabs including figuring, painting, etc., complete.	Each	16
5	Do index stones do	"	16
6	Do date stone do	"	1
7	Do Registered No. stone do	"	1
8	Do bench mark stones do	"	2
9	Do gauge stone 12' high do	"	1
	II Sluice—		
1	Cutting and opening the bund for examining and repairing the damaged portion.	Lump	sum Rs.
	III Waste weirs—		
1	Left masonry, plastering and repairing here and there	Lump	sum Rs.
2	Right Natural clearing the draft channels for the clear discharge of water.	Lump	sum Rs.
	Total ..	....	....

Dated 16th April 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Shimoga Division, up to 31st May 1920, for constructing Mugalihalli, Mugalikatte tank, Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Mugalihalli, Mugalikatte tank, Channagiri Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Mugalihalli, Mugalikatte tank, Channagiri Taluk.

Item No.	Items of work	Per	Quantity
	First bund at R. L. 55·00 and top width 6′ throughout—		
1	Clearing bushes and cutting trenches wherever necessary	Lump	sum
2	Earthwork to bund including watering, tamping and consolidating, etc., complete.	C. yd.	10,894
3	Turfing front and rear slopes of bund	S. yd.	8,330
4	Providing and fixing grade stones with bed slabs including numbering, pointing, etc., complete.	Each	19
5	Index stones	,,	19
6	Date stone, chiseling painting, cutting figures, etc., complete	,,	1
7	Registered No. stone do do	,,	1
8	Bench mark stones do do	,,	2
9	Gauge stone 12′ high do do	,,	1
	Second constructing sluice No. 1 at R. L. 43·50—		
1	Earthwork cutting open the existing bund and refilling the same with consolidation.	C. yd.	113
2	Earthwork excavating foundation	C. ft.	10
3	Filling in foundation with concrete	,,	270
4	Burnt brick in surki mortar	S. ft.	192
5	Burnt stone slabs dressed	Sq.	65
6	Plastering with surki mortar	R. ft.	3
7	Providing and fixing cast iron pipe 9″ diameter including cement pointing of joints and carriage to site, etc., complete.		45
8	Providing teakwood plug with well cut shoulder orifice plug and guide wholes.	Lump	sum
	Third constructing a sluice No. 2 at R. L. 49·00—		
1	Earthwork	C. yd.	2
2	Filling in foundation with concrete	C. ft.	42
3	Burnt brick in surki mortar	,,	80
4	Burnt stone slabs dressed 4″ to 6″ thick	Sq. ft.	11
5	Plastering with surki mortar	Sq.	1
6	Providing and fixing cast iron pipe 9″ diameter including cement pointing of joints carriage to site, etc., complete.	R. ft.	27
	Fourth waste weir masonry 100 feet long at R. L. 50·00—		
1	Earthwork	C. yd.	146
2	Clearing approach channel	,,	170
3	Surki concrete	C. ft.	234
4	Burnt brick in surki mortar	,,	1,347
5	Burnt stone slabs dressed 4″ to 6″ thick	Sq. ft.	328
6	Plastering with surki mortar	Sq.	925
7	Rough stone work new with jelly packing	C. yd.	100

K. NARAYANA IYENGAR,
Executive Engineer.

MEDICAL DEPARTMENT.

EPIDEMIC DISEASE HOSPITAL.

NOTICE.

Tenders are invited for the supply of diet articles, etc., required for the use of the Epidemic Disease Hospital, Mysore, for six months from 1st July 1920, *vide* pages 219 and 220, Part VI of the *Mysore Gazette*, dated 15th April 1920, or apply to the undersigned for particulars.

C. RAJAGOPAL,
Medical Officer,
Epidemic Disease Hospital.

CIVIL HOSPITAL, CHITALDRUG.

Notification dated 18th April 1920.

Notice is hereby given that sealed tenders will be received at the above Hospital up to 10 A.M., on Monday the 17th May 1920, by the District Medical Officer, for the supply by contract of all articles of diet, etc., as per annexed list required for the use of the above Hospital, for six months from 1st July 1920 to 31st December 1920.

2. No tender will be received after 10 A.M. on the 17th May 1920.

3. Tenders to be superscribed "Tenders for the supply of provisions for the Civil Hospital and Dispensary, Chitaldrug." The form of the tender is given below.